

# STIMA COSTI DI COSTRUZIONE KINDERGARTEN MBAMBA BAY

## COST ESTIMATES FOR THE NEW KINDERGARTEN AT MBAMBABAY

The following list is the estimates for the Kindergarten expected to be built at Mbambabay.

- Corrugated iron sheets 225pcs @ 17,000/=	3,825,000/=
- Cement 240 bags @ 18,000/=	4,320,000/=
- Burned bricks 48,500 @ 80/=	3,880,000/=
- Stones 38 trips @ 50,000/=	1,900,000/=
- Gravels 12 trips @ 90,000/=	1,080,000/=
- Sand 30 trips @ 10,000/=	300,000/=
- Timber for roofing 410pcs @4,500/=	1,845,000/=
- Nails 50kg @ 3,500/=	175,000/=
- Paints 5 buckets @ 85,000/=	425,000/=
- Toilette sinks 10pcs @ 45,000/=	450,000/=
- Doors 9pcs @ 150,000/=	1,350,000/=
- Windows 23pcs @ 85,000/=	1,955,000/=
- Facial board 30pcs @5,500/=	165,000/=
- Plastic water tanks 2 @ 650,000/=	1,300,000/=
- Transportation of above items	1,500,000/=
- Labour charges	<u>4,575,000/=</u>

**TOTAL COST FOR THE WHOLE PROJECT** 29,045,000/=

Hanga Abbey will be able to provide for the labour charges -4,575,000/=

**Funds needed to construct the Mbambabay Kindergarten** **24,470,000/=Tsh.**